

MARITIME GRAVEYARD

BENV GA08: DESIGN REALISATION STEVEN DANIEL GRAVES





CONTENTS

00 MARITIME GRAVEYARD, AN INTRODUCTION 0.01 Brief: Museum of salvaged shipwreck 0.02 Project Research + Background 01 BUILDING FORM, SYSTEMS, PLANNING + CONTEXT [40%] 1.01 Project Synopsis 1.02 Stockholm 1.03 The Site 1.04 Site Restrictions 1.05 Scheme Development 1.06 Scheme Development 1.07 Scheme Development 1.08 Site Response 1.09 Programme + Organisation 1.10 Climate Overview 1.11 Climate - Physical Testing 1.12 Climate - Physical Testing 1.13 Structural Overview 1.14 Site Plan 1.15 Access, Circulation + Means of Escape 1.16 Floor Plans 02BUILDING CONSTRUCTION [15%] 2.01 Construction Sequence 2.02 Construction Sequence 2.03 Construction Sequence 2.04 Structural Systems - Introduction 2.05 Structural Systems - Overview 2.06 Structural Systems - Stresses 2.07 Material Strategy - Glass 2.08 Material Strategy - Steel 2.09 Material Strategy - Timber 2.10 Cross Section 03PERFORMANCE [30%] 3.01 Environmental Principles 3.02 Environment - Solar Strategy 3.04 Environment - Solar Strategy 3.05 Environment- Physical Testing 3.06 Environment- Physical Testing 3.07 Environment- Ventilation 3.08 Environment- Rainwater Strategy 3.09 Environment- Water Filtration Strategy 3.10 Environment - Solar Strategy 3.11 Environment - Lighting Strategy 3.12 Environment - Lighting Strategy 3.11 Environment-Physical Testing/Future Development 04BUILDING DELIVERY [15%] 4.01 BUILDING DELIVERY - Delivery and Building Parameters

BIBLIOGRAPHY

4.06 Plan of Works

4.02 BUILDING DELIVERY - Health and Safety
4.03 BUILDING DELIVERY - Health and Safety
4.04 PROCUREMENT - Form, effect upon design
4.05 PROCUREMENT - Form, effect upon design



o.o1 STOCKHOLM, AN INTRODUCTION BRIEF: THE MARITIME GRAVEYARD

SITE

Land Adjacent Biskopsvägen 19, 115 21, Djurgarden, Stockholm, Sweden

PROJECT SYNOPSIS: THE MARITIME GRAVEYARD

The project brief is a 'live' museum displaying shipwrecks that have been preserved in stockholms archapelago. The submerged wrecks are to be brought on land to help reduce their environmental impact on the landscape and the new Architecture will be used to salvage these sunken wrecks and displaying them as artifacts. This architecture should question the notion of 'a musem' as a civic monument and critique the way that these cultural destinations can become disconnected from their localities. This proposal should therefore act as a piece of social infrastructure.

The project should have a responsivity to its environment and dynamically evolve throughout time to empower the artifacts it houses and create momentary conditions reflective of its environment.

SCOPE OF WORKS

The proposal acts as an extension of Stockholms Archipelago, habitating the south coast at Biskopsvägen, on 'the museum island' Djurgarden. The littoral zone is extended North-Easterly onto the site and spreads through Djurgarden carving the landscape to form an organic network of channels and docks.

CONSULTANTS

Andrew Porter, Abigail Ashton and Tom Holberton - Unit 21 Design Tutors: The Bartlett School of Architecture UCL

Brian Eckersley - Structural Consultant: Eckersley




0.02 PROJECT RESEARCH +BACKGROUND



CONTEXT: An Introduction to Stockholm

Stockholm, the capital city of Sweden is a city with a strong connection to water. The city is built across fourteen islands that are connected between fifty-seven bridges giving it the name the 'city between the bridges'. Located on the threshold between lake Malaren, the third largest *freshwater* lake in Sweden and the Baltic sea the cities ties to the water are incredibly strong. The secularised city becomes interconnected through bridge links. These bridges are incredibly important vessels to provide physical connectivity. However the fragmented nature of Stockholm and its Archipelago, *despite this framework of infrastructure* has lead to boating at the forefront of transport between the islands.




Prologue

Stockholms Archipelago, is a collection of over thirty thousand islands and rock outcrops that form the largest chain of islands in sweden and the second largest in the baltic sea. The islands are located just a few minutes by boat from stockholm forming a beautiful and breathtaking panoramic landscape. This fragmented landscape is home to an abundance of wildlife, cultivating a very rich and diverse ecosystem.

This fragmented maritime landscape has led to boats and boating, being increasingly popular with swedish people and being an important part of swedish culture. Boating is one of the largest activities in the country, with one third of the country's population taking part in boating at least once per season and the number of pleasure boats per capita being one of the highest in the world. As well as this, sweden has a highly developed boat building industry which generates export income and provides an abundance of jobs. This means boating has become a way of life for swedish people and has helped to define Swedens identity as a boating nation.

Throughout history shipwrecks have sat beneath the Baltic preserved almost perfectly on the seafloor. Making the baltic an Archaeological paradise of undiscovered maritime treasures. Historically political issues and nature have conspired to keep these secrets of the Baltic hidden with warships and submarines preserved perfectly in the sea water because of the low salt content of the water. Throughout history, it has also been tradition amongst Swedish people to take their old boats out onto Stockholms Archipelago during winter months and bed them on ice, drill holes in their hull and as the ice melts let them sink below the water. This is however creating large environmental issues, as the chemical content of the boats paint (and oil) is leaking into the archipelago, killing wildlife and damaging the enironment.

This maritime environment and the inherent nature is engrained into the swedish culture and this connection between land and sea remains important to the swedish identity.













In Sweden, materials and components from 200,000 scrapped cars are recovered and reused each year. It is part of a well-established recycling system. However the same systems are not available for boats, and due to Swedens strong national maritime interest this poses a problem.. Around 60,000 boats per year in Sweden get old, are damaged or otherwise breakdown never to see water again. The Maritime Graveyard serves primarily to recover parts from disused boats and boat wreckages and store the unsalvagable boats away from the water where they pose a threat to the environment.



Djurgarden

Djurgården is an island in central Stockholm, Sweden. It is home to many historical buildings, monuments, museums and galleries. The island is home to the open-air museum Skansen as well as a small residential area Djurgårdsstaden. There are many yacht harbours, and extensive stretches of forest and meadows. It is one of the Stockholmers' favourite recreation areas and tourist destinations. It has as a consequence, adopted the name 'the museum sialnd' attracting over 10 million visitors per year to its attractions.



DJURGARDEN - The museum island

Museums on the Island











The museums on the Island stand as disconnected elements. They house artifacts within galleries and as a result isolate them.


The buildings themselves act as cultural destinations and therefore isolated entities with the space between them acting as spaces of transition. The Maritime Graveyard will act as a piece of social infrastructure, spreading across the landscape retaining a strong connection to the waters edge and inviting people to learn about the countrys strong maritime cultural history.





1.03, Site Restrictions

TO LAKE MALAREN









TO BALTIC SEA










There is currently little interation between the waters edge and the site. The only instance where a connection occurs is shown in view 3. People here are utilising rock faces for site seeing out onto the water. This is an important vista to retain a visual connection to the opposite islands.

The massing of the site should take in to consideration the connection through the corridor to the water. Boats should be able to travel on to the site and the vidual link out on to the water must be retained.

The role of the water within the scheme is vital. The Archipelago is to be extended onto the site, spaces are to be created beneath the water and the depth of the water is to determine the intensity of light that enters the building.




 $The\ Gravey ard\ for\ Maritime\ wreckages$

Existing Site Sketch analysis



1.06 Concept + Form development


Conceptual section through the site showing theboat being brought into a new channel provided for boat wreckages to be viewed as Maritime Artifacts.



The Graveyard for Maritime wreckages

Stockholms fragmented landscape is scattered with maritime wreckages, these wreckages are to be lifted from the Archipelago where they are causing damage and pollution to the environment. These boats are then brought on to the site at Djurgarden which will act as an extension of the Archipelago where these boats will become artifacts of swedens rich Maritime history.












1.07 Concept + Form development





 $The\ Gravey ard\ for\ Maritime\ wreckages$


Initial Conceptual Gallery drawings






















1.09 Programme + Organisation


The proposed building is conceived as a cultural artefact of the Maritime history of Stockholms Archipelago. It reinforces and completes the historic identity of Stockholm. It is designed as a flexible landscape and the spaces within the scheme are to respond to programmatic adjustments in the short and long term and which could be reinterpreted in the future.

The brief for the site on the Djurgarden has been largely prescribed by the environmental crisis affecting the Archipelago. The intention is that this is a project acts as a museum of the Archipelagos lost maritime treasures, whilst also helping the environment by removing the toxic artifacts and filtering their damaging effects on the environment.

The spaces that would be incorporated into the design

- 01 Exhibition / gallery spaces
- 02 Shipwreck salvage workshops
- 03 Boathouse
- 04 Kayak rental shop
- 05 Plant rooms
- 06 Retail / restaurants / rental studios
- 07 Outdoor space

The adjacency diagram below describes the intention to extend the Archipelago on land and salvage the shipwrecks from beneath the Baltic.





Solar Analysis

Feb


Apr

1.10 SITE OVERVIEW Climate

Due to stockholms northerly geographical location, its climate is maritime temperate. The biome it belongs to is the Temperate Deciduous Forest. The North Atlantic Current makes the air temprature rise which is brought up from the South-West by low pressured winds. Due to high pressure zones in the East Stockholm recieves warm summers and cold winters.

The quality of sunlight Stockholm recieves is considerably restricted due to the amount of daylight throughout the year and also due to the intensity of this light which can often be hindered by weather. During the winter the amount of daylight Stockholm recieves drops to as little as six hours per day. During the summer however the longest day lasts for over 20 hours. aylight throughout the year and also due to the

Average daily hours of sunlight




Sunny daylight hours Cloudy daylight hours

Aug

Oct

Jun

Dec



Traditonal design considerations of the Provence evolved for the climate:

- Strong and compact, retaining warmth in winter and staying cool in summer.
- · Healthy, dry indoor climate for inhabitants
- Durability in a maritime climate with driving rain.
- High number of windows allowing maximum levels of natural light indoors.
- The building's insulation levels.
- The buildings capacity to withstand freque nt driving rain.

Historically, the Scandinavian built as much as possible out of wood. A lack of forest forced them initially to build partly underground with only the top part of the walls and roof being made of wood.

All available timber was used, such as salvaged parts of boats and driftwood. Most dwellings were made with a timber post-frame filled in with stones and mortar. Where timber was available it was always the preferred building material.










1.11 Evironmental Strategy Environmentally Responsive Device






















Solar Tracking Apparatus

Planning sketches for Solar Tracking device. The apparatus takes directional light readings and through an Arduino circuit board, translates this information to drive two 9g metal gear servo motors, the directional light readings drives the motors in a corresponding direction. This movement is then translated to the architectural componants via a series of cables in tension. This apparatus is to act as a starting point for a piece of infrastructure that will span the landscape and translate solar activity on both a long and short term basis. This means the apparatus will respond to immediate changes in its surroundings effectively, this will allow the corresponding architecture to adapt to the slightest of changes in light. This includes momentary overshadowing from cloud formations, passing traffic, etc.




1.12 Evironmental Strategy Environmentally Responsive Device

















1.13 Structural Strategy Structural Overview









Water Channel above gallery space -Glulam ribs with structural glass





Sub-terranian gallery space supported by concrete retaining walls



Site Section NTS









2.01 Construction Process

Construction Sequence(1) - Showing construction sequence of key structural elements and infrastructure



Waste Disposal Site


Satelite map showing the location of the proposed site (Bottom) and the waste disposal site for any non recyclable waste(Top).

Construction Sequence Key

1 Vehicular access for works traffic established. The Existing site is cleared of debris, the debris is cleared up and disposed of. The Existing trees within proposed building envelope are removed and stored on site to be prepared for use within the building. Area of rock outcrop removed and stored on site. Section of wall removed.

2 Sections of earth excavated, material removed and stored onsite for later use. Some areas excavated for temporary access to new lower ground level. New sheet piling installed to provide dry zone for new pile foundations to be formed.

3 New piling extending in to temporary dry zone to be submerged in water at completion. Sheet piling provides dry access for works. Mechanical pump systems prevent water ingress. Temporary sheet flooring laid out for storage of construction materials, vehicles and amenities.





Temporary sheet flooring

The Existing site is cleared of debris, the debris is cleared up and disposed of.

The Existing trees within proposed building envelope are removed and stored on site to be prepared for use within the building.

Area of rock outcrop removed and stored on site. Section of wall removed








Sections of earth excavated, material removed and stored onsite for laters use (APPROX.)

Excavated for temporary access to new lower ground level.

New sheet piling










2.02 Construction Process

$Construction\ Sequence (2)\ -\ Showing\ construction\ sequence\ of\ key\ structural\ elements\ and\ infrastructure$



Vehicular access steelwork installed across site ribbed structural system installed

Water flow control mechanism installed

Lightwells formed


Construction Sequence Key


4 Trenches for steelwork across site are to be created and steel componants are installed. Structural elements within the excavated trench are installed in sections and covered to prevent water ingress during heavy rain.

 ${\bf 5}$ Precast structural cores are shipped to site and constructed

6 Remaining external steel grids are constructed. Jetty elements extending into Archipelago are built. Trench walls are tested for whater tightness. Dry zone is removed.

7 Floors are cast. Precast facade elements and glazing are brought to site and installed. Channel tested for water tightness. Channel to be filled for a period of 1 month to ensure no water ingress damages the internal evironments. Internal spaces are created.







W


Construction Sequence(3)

		Aug Son Oct Nov Doc lon Eat Markon Mailing Ind
NARLING / STRIP OUT WORKS	Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Jan Feb Mar Apr May Jun Jul	Apr MayJun Jul Aug Sep Oct Nov DecJan Feb MarApr MayJun Jul Aug Sep Oct Nov
Removal of debris		
Existing trees removed and stored on site		
Creation of vehicular access route		
FIRST PHASE OF WORKS		
Sections of earth excavated and used elsewhere for levelling out (excess stored onsite)		
Sections of existing concrete decks excavated and recycled for use elsewhere onsite		
Excavated land supported with temporary structure for casting to take place		
Temporary roofing installed		
Casting of Subterranian base and inbuilt channels		
Casting of retaining walls(including waterproofing), butresses and concrete bearing elements		
Sheet piling and pump installed		
Second phase of excavation at existing line of coast with temporary structure		
Installation of reinforcement		
Casting of base for ground level buildings		
Steel basework installed		
New deck installed over plling		
Concrete apron cast at coastline		
Sheet piling removed	•	
Precast concrete cores erected		
Steelwork installed on structural cores		
Steelwork for internal linings and walkways installed		
Wall linings including waterproofng works		
Temporary roofing partially removed for glulam roof structure to be installed		
Partition walls erected		
Prefrabricated glazing installed		
Joinery installed		
SECOND PHASE OF WORKS		
New ground level steel framed structures erected		
Structural walls and cores erected		
Second floor installed		1
oofing works (complete envelope)		
Ground works build up of pathways and planting		1
Glazing installed		
Joinery installed		
Claime Inoqued		
Exhibitions internal environment checked for water ingress		
JTERNAL ELT OLITS		
Specialist exhibition pieces installed		
Internal Furniture installed		
77 77 77 77 77 77 77 77 77 77 77 77 77		
OFF SILE PREPARATORY WORKS		
Fabrication of concrete structural cores		
abrication of steel elements and fixings		
Fabrication of structural and non structural glazing		
< <		
SPECIALIST WORKS		
3D Scanning of internal environment		
Calibration of environmental control systems		





2.04 Structural Sytsems Structural Focus Overview


Within Section 2 I will focus on the structural system involved in the subterranian gallery space. I will show the development and detailing of the structural system.



This section through the subteranian gallery sits within a trench beneath ground level and so will require retaining structures and weatherproofing. The space is situated beneath a body of water which transports boats above. The body of water is controlled so the depth can be adjusted to alter the amount and quality of natural light that enters the gallery space. In order to support this body of water as well as the boats above I have developed a structural system be replicated across the site in museum spaces where the same conditions are required.







A Salvaged boat being transporte on to site

B Body of water flooding the site from stockholms Archapelago

C Timber Clad ramped walkway and handrail

D Timber clad walkway through the exhibition space

E Salvaged boat suspended and exhibited within the museum

F Steel grid framework supporting suspended boat and walkway above

G Structural grid tied back to retaining walls with ertical loads being distributed vertically into pad foundations

H Body of water shown in situ

I Steel suspension cables vertically suporting the glulam ribbed hull structure, tied back to concrete structural core

J Marine grade triple glazed armoured glass unit supportin boady of water above cladding glulam ribbed hull structure

K Glulam Ribbed hull structure braced horizontally by timber mullions and tensional steel element

L Tensional steel element fixed to each structural rib

M Timber column transferring vertical loads from ribbed structure above

N Steel beam clad in precast concrete sections transferring loads horizontally to pad foundations

O Concrete bearers transferring loads from ribbed structure vertically through the retaining wal to pad foundations below - also acting as butresses


P Concrete retaining wall


Q Step in retaining wall (degree of step)

R Retaining wall housing water depth and flow channels

S Retaining wall heel to counter rotational movement

T Body of earth





2.08 Structural Sytsems **Material Strategy - Steel**

Steel is used in construction as it has many advantages. Mainly its strength to weight ratio. Steel componants for the Martime Graveyard will be made offsite and transported to be utilised within the scheme. Bespoke componants and connections will be created by specialist steel fabricators who are employed to produce these elements offsite. One delievered to site the contractors will assemble the finished componants. Each steel connection is to be designed by the Architect and consuting Engineer. This is critical to the project as most structural failures happen at connections. Its is because of this that the consulting engineer, steel fabricator and Arcitect work closely together to give accurate design drawings to the fabricator for the connections and within the drawing package, clear assembly guidelines are given

to the contractors to follow. The fabrication of the steel structure can be done entirely at the construction site, however this is labour-intensive. By fabricating finished componants offsite in a workshop, better working conditions are provided and the time spent producing the structure is reduced. The contractors are challenged with simply lifting the componants in to position and bolting them together to form the structure. If the componants were produced on-site, the quality of the compinants might suffer with the poorer lighting conditions and availability of


specialist equipment.

The length of the componants are goverened by the size of truck and trailer that is available to transport them onsite. The steel componants that make up the gallery space have been designed so they are never longer than 6m. This means they can be transported to site easily. (Standard transport lorry trailers can transport up to 12m)

As the on-site work is limited to lifting the members into place and bolting them together. The construction process is extremely fast.




Multiple Spider Cranes will be used to lift the steel elements in to place during construction within the gallery space only. This will be used as its easily manouvered into tight spaces and as the max. length of the steel componants is never greater 6m they are able to support this weight with ease.



The central structural steel beam is visually continuous which spans the gallery space, is supported by horizontal members at 3m intervals.

Due to the length restrictions beam to beam connections allow this componant to be built up of 6m steel lengths.

The beam is clad for fireprotection, this also conceals the flanges of the beam where services are provided discreetly for the gallery. The beam also acts as a temperature controlling element provided fresh thermally treated air into the gallery space.



Typical connection detail at steel to steel joints

L brackets

beam

tied to steel column and."

Typical central beam to beam detail

> Central connection plates are welded to the beam and bolted to eah other

Connections contain strengthened openings for the services to breach

welded to column


Typical detail

column connects

to concrete base

where steel

Haunching on concrete pad provides lateral stability







The high strength and stiffness of laminated timbers enable glulam beams and arches to span large distances without intermediate columns, allowing more design flexibility than with traditional timber construction. The size is limited only by transportation and handling constraints.



Glulam as a material optimises the structural potential of a renewable material resource. Large members can be constructed off site and shaped easily which lends itself to the unusually shaped channel. The process of making glulam means there is significantly lower amounts of waste material compared to solid sawn members. The negative impact of knots within each board that build up the beam is significatly less also.

The weight of Glulam is two-thirds of that of the weight of steel and one sixth the weight of concrete – the embodied energy to produce it however is six times less than the same suitable strength of steel.





Environmental principles

A Solar gain/exposure to natural light

B Low perimeter walls to allow maximum solar light

C Triple Glazing

D Body of water - Depth and Terbidity are adjustable

E Responsive Automated Louvre System


F Internal Gallery Space

G Draining filtered water and transporting it back to the Archapelago


H Concrete elements add thermal mass which regulate temperature


I Temperature regulating beam

J Heating matrix within walls











3.04 Environment **Solar Strategy**

SOLAR RESPONSIVE SYSTEM Physical development




Louvre system fixed to u/s of parallel sections of glazing (directly above walkways)


If internal Lux levels raise above 300 Lux. the Louvre system closes completely blocking 100% of the solar rays through the flat glazed pannels above the walkways. When they drop below 50 Lux the Louvres are fully opened. The percentage of solar gain blocked between these extremes is incremental to keep glare and temperatures within the space steady.



Motors pulling tension cables that drive louvre systems, channel drainage and water filtration.


Directional light sensor






Arduino system controls the rate of water drainage in the channel. This Axon shows the system that will drain the channel driven by the horizontal motors. As Light levels rise the draining of the channel is reduced so more water remains in order to reduce glare within the gallery below and keep the internal tempreatures down.

The light resistors drive the connected motors to a limited degree.





See Appendix, for Anduino

If internal Lux levels raise above 300 Lux. Water levels in the channel are raised. When they drop below 50 Lux the water level is dropped. Artificial interna lighting helps to regulate the levels.



model - This simuates the actual responsivity of the building













3.05 Environment Solar Strategy - Solar Responsive Device


The incoming light energy is concentrated on the light depending resistors by the convex lense. This is then broken into directional data by the x shaped divider

































3.07 Temperature and ventilation



Month of year	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Year
	01	02	03	04	05	06	07	08	09	10	11	12	1-12
Dominant wind direction	~	~	~	~	7	~	~	~	~	~	~	~	~
Wind probability >= 4 Beaufort (%)	31	31	39	43	44	39	35	32	34	32	31	35	35
Average Wind speed (kts)	9	9	10	11	11	10	10	9	10	9	9	10	9
Average air temp. (°C)	-2	0	3	9	14	18	21	20	15	8	4	0	11



Wind Direction Distribution charts (%) for most popular visitor months



Disadvantages of mechanical ventilation

The disadvantage of mechanical ventilation is that it consumes electricity and cools the air. Therefore, mechanical ventilation should be kept to a minimum of the acceptable levels of indoor air quality.

Providing more ventilation than is really required increases costs. This is because internal 'conditioned' (heated or cooled) air that is removed from a building has to be replaced with the same amount of air from outside. This also needs to be heated or cooled to match the temperature of the building. Besides, moving air around mechanically, using fans uses electricity.

Indoor air quality is important to the occupants of the buildings, comfort. To provide a safe, healthy and comfortable indoor environment, minimum ventilation standards must be provided. This is dependent on the occupancy and functionality of the space. Ventilation provides the following;

Fresh air for respiration, Control of humidity (excess humidity occurs from water vapour in the air – issues arise when there are delicate exhibitions) Provides thermal comfort to occupants, Dilution and removal of airborne pollutants.

The basic standards of ventilation as defined by local authorities are Min. required fresh air – 5l/s per person with a recommended rate of 8l/s per person.

The space will be partly mechanically ventilated as opposed to relying entirely on natural ventilation because of the subterranean position of the gallery which makes it more difficult to draw fresh air into the space. There is however an opportunity to open windows or doors in the case of temperatures rising at a higher capacity.

Ventilation Calculations

Gallery Area 720.00sqm

Total Gallery capacity during peak times will be approximately 100 people at any time.


The Gallery will have 100 people present at any time each producing approx. 100 Watts of energy (most of which is expended as heat). Therefore;


10,000 Watts / 720 sqm = 13.8 Watts per sqm


In order for a room to be cooled solely by natural ventlaton, the space requires openings that cover 5% of the total foor area, on opposite sides. For the restaurant area, the opening will need to be a minimum of 36sqm Current area of openings = 16.00 sqm (8 access tunnels)

The capacity of 100 people will therefore mean the space will need to rely on suplementary ventilation to produce a comfortable environment.


3.08 Environment Rainwater Strategy









humidity of the internal space.







The colour of water is greatly affected by the suspension of particles in it. Its colour is directly affected by the type of solids that are suspended. When a body of water is completely free of suspended solids its clarity would allow light to pass freely through the water. The only limiting factor in this case would be the ability of the water itself to allow light to pass through.

Light wavelengths would be able to penetrate roughly 300ft into a body of completely pure water and the waters appearance would be blue. This is because the last colour of the light spectrum is blue.

In shallower and more turbid water the light at the blue end of the light spectrum is not absorbed into the water very far giving the water a blue appearance. However as the body of water is at its deepest in the channel is 3.5 meters the type of silt within the the water has the greatest effect on the colour of light that passes through.

The differences in colour are therefore based on the depth that specific light can penetrate without being fully absorbed but also the type of silt the water carries. These are both aspects that can be adjusted wthin the scheme to control colour of light in the gallery space beneath.

Typical water colour dependant on the type of solids within water

Green - abundance of algae

Yellow - due to clayey turbidity

Brown - abundance of diatoms


Ferrous metals -


of light.

The colour of turbid water (based on type of suspended matter rather then water depth) can therefore be adjusted through different levels of filtration.

As salvaged boats are leaking oil into the body of water oil is to be considered as it will affect the ability of the light to penetrate the water.

With oil - a thick film is produced on the water surface. This is because oil is hydrophobic and therefore floats above water. So the lightin this instance reflects upwards from the top of the film and also the underlying interface between the oil and the water. Stopping almost all of the light penetration into the water. This is therefore also to be filtered in order to control light penetration.





Turbidity is the cloudiness of a fluid caused by the suspension of particles within the fluid. These particles are generally invisible to the naked eye however they can cause the opacity of water to decrease, this will directly affect the amount of light that is able to pass through the water. Turbidity is usually used as a test of water quality. The existing turbidity of the Archapeagos water is utilised in the scheme throughout different times of the year depending on the strength of the natural daylight.


This is controlled initially by the light sensing device that controlls the level of water in the water channel. By draining water along the channel water can be drawn in at the channel source and the rate at which this water is drawn in effects the rate of filtration. So this rate is adjusted throughout the year to maintain a stable level of glare and heat within the space below counteracting the changing nature of the seasons.


Low Turbidity - Clearer water - More Solar Gain Useful in winter months

High Turbidity - Darker/Cloudier water - Less Solar Gain Useful in summer months



Turbidity is used to determine the concentration of suspended particles in a sample of water by measuring the incident light scattered at right angles from the sample.





3.11 Environment

Solar Strategy Water Filtration

Despite light being essential for viewing exhibits, it can also damage sensitive items within the gallery. Light can damage pigments within materials causing fading in the exhibited boats or change of appearance. It can even cause damage to already sensitive materials. Light is expressed in wavelengths, with natural light starting with a wavelength of 300nanometers(this is the minimum wavelength able to penetrate the atmousphere. The light spectrum can be divided into 3 main groups (see the table below)


The light between 400 and 760nanometers is visible light that our eyes are able to see as the spectrum of colours visible in a rainbow.

Wavelengths shorter than 400nanometers are UV radiation. This radiation is not visible to the human eye, this shortest wavelength is the most damaging.


Wavelengths longer than 760 are classed as Infa-red radiation and is felt as heat.

It is therefore important to reduce non visible light - particularly UV light. This is the job of the body of water as UV and Infared lights penatrative ability of water is lesser than that of light with different wavelengths.


So to eliminate non visible radiation the body of water is kept at a depth during times where light levels are highest - to a maximum. Giving the Gallery a blue hue (blue light having the highest penatrative ability in water.



This shows the spectrum of light and its penatrative ability in water. This will be relevant within the channel above the gallery space as the penatrative depths will be reduced with Turbidity. Making the 3.5m deep channel have a strong effect on the internal environment.



















3.12 Environment

Solar Strategy Water Filtration




This shows the spectrum of light and its penatrative ability in water. This will be relevant within the channel above the gallery space as the penatrative depths will be reduced with Turbidity. Making the 3.5m deep channel have a strong effect on the internal environment.





Pages act as a document for the calibration of lighting systems post construction. This allows the internal spaces to be tweaked to optimise the internal environment as per the visual mock up.




Artificial lighting supplementing the overall lighting making a comfortable environment. Focusing on the exhibitions to provide visual focal points.




High levells of solar gain






300nm 400nm 760nm →
Ultraviolet Violet blue green yellow orange red infrared





3.13 Environment **Arduino Development**






The Arduino board is a simple way of producing a set of commands used in the physical testing. The application of the system within the building would need a system that is more sophisticated and reliable. The system wouldn't necessarily be entirely digital as the analogue nature of the system produces movement within the gallery space that effects the experience of the museum

Issues with scaling up the solar tracking device.


As the lense is scaled up the strength of the lense needs to be restricted in order to not damage the solar resistors

The LDRs will need to be replaced with a more sophisticated and reliable

The number of light sensors will increase, which will provide a more accurate reading of light direction (compared to the current responsivity in




By reversing a fresnal lense directional light can be focused on a specific point. These lenses can be positioned in different directions and so the highest lux. levels recorded will be picked up by the smart system and the building will respond accordingly.




It is possible to use a series of the lenses used within the physical testing. They will need to make up larger network as shown below. This proposal shows a section through a domed configuration of lenses which focuses the natural daylight in the center.

3.12 Environment

Solar Strategy Water Filtration




This shows the spectrum of light and its penatrative ability in water. This will be relevant within the channel above the gallery space as the penatrative depths will be reduced with Turbidity. Making the 3.5m deep channel have a strong effect on the internal environment.





Pages act as a document for the calibration of lighting systems post construction. This allows the internal spaces to be tweaked to optimise the internal environment as per the visual mock up.




Artificial lighting supplementing the overall lighting making a comfortable environment. Focusing on the exhibitions to provide visual focal points.




High levells of solar gain





300nm 400nm 760nm →
Ultraviolet Violet blue green yellow orange red infrared





4.01 BUILDING DELIVERY Delivery and Building Parameters


LOCAL CONTEXT OUTLINE, DELIVERY + BUILDING PARAMETERS CLIENT ORGANISATION

The Swedish National Maritime Museums (SNMM) will be the client. A government agency under the directive of the Swedish Ministry of Culture who will approve the project and budget. SNMM also runs the Vasa Museum, Maritime Museum and Naval Museum. A supervisory board of elected individuals from the SNMM group and representatives from the Ministry of Culture and Swedish environmental protection agency will approve the development. Ensuring the project addresses and meets the national environmental and cultural objectives.

PROJECT Environmental AIMS + cultural GOALS

The project aims to preserve Sweden's rich national maritime cultural heritage and to provide a platform for people to appreciate its legacy. The environmental issues remain core to the ethos of the museum, and the proposal will help with the governments environmental objectives to preserve Stockholm's marine environment and create a flourishing coastal area.

It will aim to do this by providing a facility to dispose of old boats and remove toxic wrecks from the archipelago that are contaminating the natural environment and causing harm to biodiversity. The wrecks will be salvaged and then placed in the museum to exhibit otherwise lost treasures of Sweden's rich maritime heritage.



ROLE OF THE ARCHITECT

- · Formally advise client of their duties/responsibilities
- · Take on role of Principle Designer
- · Advise client on specialist contractors
- Development of brief advising the client on the proposed scheme design
- Consulting with maritime specialists to define scheme parameters.
- Examining the site conditions and Coordinating Consultants
- · Collate specialists' documents and reports
- Undertaking a feasibility study within parameters defined from measured survey drawings and specialists reports
- · Preparing sketch plans for approval from local authority
- · Applying for Planning Permission
- Provide services in connection with any planning appeals that may arise
- · Preparing preliminary specifications
- Work up drawings to a standard required to meet building regulations requirements
- Provide the contractors with construction drawings and specification
- Upon completion provide as built and health and safety documentation to the client

ROLE OF THE CLIENT

- Ensure suitable management arrangements are in place for the project
- Select and appoint a competent Principal Designer (Architect)
- Select and appoint a competent Principal Contractor and Specialist Contractors
- Oversee budget and brief concerns
- · Notify the relevant authorities of the project
- Ensure provisions of time and resources are provided for each stage of the project
- Provide suitable welfare facilities prior to construction
- ensure that contractors are provided with the necessary

The Design Team + Specialist contractors
The consultants necessary for the project will include

- · Cost consultant.
- · Mechanical and electrical engineer
- Structural engineer.
- · Access consultant
- Approved building inspector
- Archaeologist
- · Civil engineer
- · Construction manager
- Contract administrator
- · Ecologist
- · Environmental consultant
- · Fire engineering consultant
- Fixtures and equipment consultant
- Health and safety consultant
- · Hydrologist
- · Landscape architect
- Local consultants with specialist knowledge of local practices and procedures
- Lighting designer
- Planning consultant
- · Public health consultant
- · Quantity Surveyor
- Security consultant
- Site inspector
- Specialist contractor for excavation and building envelope
- Specialist contractor for sensitive interior spaces
- Surveyor
- · Transport engineer

Prior to the project starting it is vital that the design teams are well coordinated and structured. The design team may change throughout the project however the structure of the project will remain in line with

Appointment of the Architect

As the project is Government funded, the architect would be appointed following a tender procedure. The successful design and construction team would be chosen from a pre-qualified short listing process. They would need to meet European Union requirements and be the successful candidate in a design competition with a competitive tender price. The architect is responsible for ensuring the design team and expert specialist consultants work within local building regulations professional practice. The architect will provide onsite supervision at every stage of the project.

STAKEHOLDERS

The major stakeholders will provide the funding for each stage of the project. These are the Swedish Ministry of Culture and Swedish environmental protection agency who provide funding for projects that work towards the environmental objectives that the government wish to address by 2020.

> European Environ Agency, EEA





Governments Environmental objectives



4.02 BUILDING DELIVERY Health and Safety

Building Delivery/Health and safety

CDM REGULATIONS - DESIGNING OUT RISK


The Construction (Design and Management) Regulations 2015 are a set of legal documents outlined by HSE (health and safety Executive). They are designed to govern the way all building projects are planned and undertaken irrespective of size to ensure the health and safety of those involved in the construction industry. The document aims to improve health and safety by helping plan the works so risks are identified and managed from start to finish.


RISKS MANAGEMENT - NEW ROLE OF THE ARCHITECT

As previously mentioned, the Architect will take on the role of Principle designer. The principal designer has control over the pre construction phase of the project. This will be the case because the Architect has

- · a sound technical knowledge of the construction industry
- understands the skills to manage and coordinate the preconstruction phase Although the client has overall responsibility for the successful execution of the project, the principal designer and principal contractor will take lead on different phases of the project.

The principal designer and contractor are key in coordinating health and safety so its important a good working relationship is established.





The project will require a summary of potential risks to the construction crew for the entire duration of the project and its use afterwards. The following list identifies risks and defines the control methods that are to be undertaken.

Identify the Hazard(s):

Using the list of hazards supplied tick all those that apply to your design specification; remember to include any potential risks to construction workers, setting crews, production staff, performers, audiences or members of the general public.

Assess and Control the Risk:

Complete the full risk assessment by adding in the control methods needed for each hazard identified. If you have additional hazards which are not identified in the list of hazards supplied, add these together with the control measures needed onto the last page of this document

Existing Site


Task/Activity	Identify Hazard	Control Measures undertaken
Investigation Work	Risk of drowning – As site is located on waters edge	Anyone undertaking investigations by boat or at water's edge must be supervised by experienced professionals in suitable weather conditions.
		The coastguard is notified of the work and correct PPE is provided and worn correctly.
	Collapse of unstable Rock outcrops	No one can walk on areas of unstable ground. If its necessary correct ppe is provided and worn correctly.
Excavation	Collapse of Excavated earth	Unstable ground will be temporarily reinforced
	Persons/Material falling in to excavation	Excavations are clearly marked. Stop blocks are placed around the perimeter of excavated areas. Correct PPE is provided and worn correctly.
	Water Ingress/flooding	Dry Zones established and mechanical pump systems used to counteract ingress of water. Escape routes are defined and clearly marked.



4.03 BUILDING DELIVERY Health and Safety

continued

	Undermining of existing ediscent	Existing foundations are identified prior				
	Undermining of existing adjacent structures	Existing foundations are identified prior to construction				
		Dig test holes to determine the location				
	Compromising existing consider	of existing foundations. Dig test holes to determine the location				
	Compromising existing services	of existing services.				
		A specialist contractor is employed who is fully trained with experience				
Construction						
Construction	Falling into excavations	A specialist contractor is employed who				
formwork		is fully trained with experience				
in-situ	Collapse of formwork	Correct formwork edge protection is				
	Collapse of formwork	provided				
Pouring	Eye, skin and respiratory tract irritation	Use correct PPE and provide washing				
Concrete in- situ	from exposure to cement dust	stations and separate eating/drinking locations in dust free areas.				
3110	Overexertion and awkward postures	Workers are to take regular breaks and				
		rotate in shifts				
	Slips, trips and falls	Identify and fix all slippery surfaces, damaged ladders, loose walkways and				
		unsteady hand/footholds.				
	Chemical burns from wet concrete	Wear correct PPE and clothing				
	Injury from equipment	Adequate lock out systems and guards provided on all machinery				
		Use respirator				
Lifting heavy	Workers may be struck by machinery or	Site Work is to be coordinated so				
building	elements being moved	workers are aware of elements being lifted.				
components with large machinery		inted.				
-		Number of elements onsite being lifted				
		is restricted to one at any time. Correct PPE is worn correctly at all				
		times.				
		Specific training is provided for all				
		workers. Maintain a safe working distance				
		between co-workers				
	Damage to existing powerlines	There are designated spotters to ensure				
		no machinery of building components enter within 20 feet of the services				
Working at	Falling	Working at heights will be avoided				
height	100.13.24	wherever it is possible				
		Safe working platforms are provided an barriers/handrails are constructed				
		Ladders are only used in areas where a				
		secure hand hold is available				
		All workers are to have received specific training				
Movement	Collision of vehicles	Designated areas and strategic planning are defined for the movement of				
of vehicles		vehicles around site				
	Being hit by a moving vehicle	Reversing is kept to a minimum				
		Construction site and welfare facilities				
Risks in	Risk of drowning in channels and pools	are separated All children under the age of 14 must be				
building use	of water	accompanied and supervised by an adu				
		at all times				
	Slippery Surfaces	Railings (min. 1000mm) high to be provided along edges of all pathways				
	Tripping on steps and ramps	Non slip surfaces are provided around				
	0	all water edges				
	Falling into subterranean gallery spaces					
	Cleaning windows at height	Extension poles used in preference of ladders				
	Cleaning guttering at height	Safe platforms are provided with access				
	and the state of t	routes and handrails				





4.04 Procurement Form, Effect upon Design and design information


Procurement Form, Effect upon Design and design information


Deciding on Procurement Method

Quality – This is incredibly important within the scheme as the Maritime graveyard holds sensitive and delicate exhibits.

Cost – The budget can be stretched and overspend is less of an issue as the proposal is helping towards the governments aims of enhancing and preserving the natural environment and cultural heritage of Sweden.

Time – The proposal will cause little interference with the surrounding landscape due to its geographical location therefore this is less of a factor within the project.





The choice of procurement method is vital to the project, choosing the best solution for the project will help to optimise the relationship between time, quality and cost. In such a large scale project a comparative study will provide an indication of the suitability of different procurement methods.

The project will be holding sensitive exhibits so quality of construction is essential, for this reason I will compare and contrast management and traditional procurement methods as these have a degree of build quality assurance. This in contrast to a design and build procurement method which is focused mainly on a trade-off between time and cost.

Traditional Procurement

The traditional procurement route, is possibly the most commonly used method of producing building works. This method is often referred to as the Design-Bid-Build method. The client initially appoints consultants to design the project in detail > prepare tender documentation (incl. Drawings schedules and quantities). > Contractors are then invited to submit tenders for the construction phase, this is done on a competitive basis.

In this type of contract the contractor is not usually responsible for the design (besides temporary works) However in this instance specialist contractors will provide their expertise in the detailed design phase.

The client will retain the design consultants during the construction phase to prepare any additional information that is required. To review any designs that are prepared by the specialist contractors, and to inspect the works to ensure quality and workmanship adheres to the proposed design. Usually one consultant would be appointed to administer the contract, in this case it would be the Architect.

This type of procurement means the design will be fully developed prior to tender which will ensure the client receives certainty about design quality and cost. However, as the contractor is appointed prior to the design development they are not able to help improve the buildability of the proposals they develop. This strategy is a low risk option for the client who wish to keep overspending rates to a minimum. The design phase will need sufficient time to fully develop the scheme and prepare unrushed and complete tender documents.


Management Procurement

Management procurement is a route of procurement where the work is completed by a number of specialist work contractors who are contracted to a management contractor. The management contractor is appointed at an early stage in the design process to take full advantage of their expertise, and incorporate their knowledge into the scheme designs as they develop. This ensures buildability. This enables some works contractors to be tendered earlier than others. This can reduce the overall length of the project. This will mean however there will be cost uncertainty until the design is complete.

This type of procurement means the client can be flexible with design matters which means that sensitive exhibitions can be altered throughout the construction process to ensure their suitability for the exhibits. It also means the contractor can contribute towards cost calculations of the works. The works are let competitively by the management contractor to subcontractors and specialists. As there is an overlap between the design process and the construction process, tender packages are made available at times that suit the construction timetable.

As the construction managers in this procurement method act as consultants to the client, the client accepts the risk for the trade and specialist contractor's/sub-contractors performance, and in some cases the client and construction manager together have not been able to impose discipline on design development, coordination and decision making. In such cases the contract manager has exposed existing weaknesses in project management capability.

Out of the two procurement types the chosen is 'Management procurement' as it lends itself to the sensitive nature of the project ensuring the highest level of buildability. Specialist contractors can undertake specific works at different times as the design continually evolves. The specialist experts of the maritime museum organisation (SNMM) will be able to oversee the construction of the project and have the flexibility to change the design as the project develops to optimise the end result.






4.05 Procurement Form, Effect upon Design and design information

Collateral Warranties

On such a large and specialised project the involvement of many consultants and sub-contractors will mean there will be many warranties. There can be difficulties with onerous terms that all parties are unable to agree to as their insurers will not provide covers. This can cause issues in attaining collateral warranties within the designated time.



Investigations, funding and programme

Investigations

Prior to the commencement of the project, initial tasks must be undertaken in order for the project to go ahead. The following investigations need to take place to ensure funding and procurement for the project.

- · A full measured survey of the existing site
- · A hydrological survey
- Arboriculture survey
- · archaeological survey
- condition survey of existing adjacent public infrastructure
- · geotechnical survey of ground and water conditions

Funding and programme.

The proposed outline for the project will pitched to the Swedish Ministry of Culture, who meet in the Spring and the Autumn to agree and discuss funding for new projects. The proposal will be submitted with an outline of works and initial budget for the Spring 2018 deadline.

As part of the Spring 2018 proposal, an outline of the programme aims and objectives will be defined. These will be in line with the Government cultural and environmental objectives they aim to meet by 2020. Within the proposal, it will be clarified that the museum will form part of the SNMM group.

The proposal will also include a brief structure for the project delivery. This will define the following:

- Key dates for the submission of specific reports and applications
- A fee breakdown for each project stage
- An overall timescale for the project

Ensuring cost certainty

From the outset of the project there must be a realistic alignment between the client's aspirations and the budget requirements. If the Architect fails to fully interrogate the feasibility of the project within the clients set parameters, the cost of the project can increase significantly. The integration of specialist contractors from the outset and continuing discussions throughout the duration of the project will minimise costly mistakes.

Working to a 'system of work stages'

To ensure the project runs smoothly within a 'system of work stages' it is important to understand the requirements needed to successfully complete the project. The key issues are:

- To understand and define a timetable when key tasks must be completed within each individual stage
- Understand the level of design required for each stage, this means avoiding producing unnecessary levels of detail where it is not required
- \bullet Understanding the expectations of other design team members at each stage



Programme delivery and quality control
The project delivery will follow the seven work stages outlined within the RIBA plan of
work 2013, "developed to ensure that the many subjects that will facilitate successful
project outcomes are considered in a holistic manner providing a Plan of Work suitable
for a 21st century collaborative project team".

	RIB	A	for a 21st	t century collabor		2.5 yrs	2 years	5
RIBA 🐇	0	01	02	03	04	05	06	07
Plan of Work 2013	Strategic Definition	Preparation and brief	Concept Design	Developed Design	Technical Design	Construction	Handover and close out	In Use
Core Objective		Devlopment of brief/project objectives/ anticipated outcomes/Proj ect Parameters Feasability study undertaken	Preparation of conceptual level design	Preparation of developed proposal. Including strategies for structure, services, systems. Initisal specification documents are provided with an outline cost.	Preparation of detailed drawings and specialist subcontractors design specifications.	Both offsite and Onsite construction occurs	Handover of building	Building in use services taken in strict accordance with the schedule of services
Procurement	Design competition advertised and design team assembled	Most suitable Procurement method established		Project Programme reviewed and discussed with client and Design Team	Project Programme reviewed and discussed with client and QS	Building contract administered	Building contract administered Site inspections undertaken	Building contract administration succesfully completed
Programme	Establish the programme for the project	The programme is reviewed with the contractors that have been appointed. Changes to programme are discussed with client			Programme reviewed by project manager to ensure deadlines are met			
Planning		Pre-application discussions and submitted once approved	Planning approved and consent is given. It is at this point that any alterations are made and refered back to local					
Key Support Tasks	Review feedback from previous SNMM projects	Preparation of Risk assesments and project execution plan	Prepare Strategy for maintainance and operations, Creation of health and safety documents. Consult with specialist contractors			Architect to visit site regurlarly to ensure build quality		
Architects Involvement	Sucessful Architect appointed following the announcement of the design competition		Architect roles are defined and the design is developed with contractor and specialist subcontractors guidance	Final plans are to be approved by client and upon doing so the technical drawing packages are created	Architect present to sign off glazing prototypes	Sign off for all building components and finishes Design ammendaments are made as bulding sectins are completed and dimensioned		
Contractors	Specialist contractors are appointed	Consultations with deign team to develope scheme			Glazing prototypes produced			
SNMM GROUP Exhibition Specialists		Exhibition pieces are 3d scanned and dimensions are taken for scheme to develop				Dimensions taken during construction and ammendaments made accordingly		